SANITARY DIVISION.

Abstract Notification dated 30th June 1918.

The attention of the public is invited to the notification calling for tenders published in pages 583 and 584 of Part IV of the *Mysore Gazette*, dated 27th June 1918, for constructing storm water drains in the Northern Extension of Malleswaram, Bangalore.

N. SUBBA RAO,
Executive Engineer.

MYSORE DIVISION.

Dated 27th June 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 15th August 1918, for restoring Ankushapur minor tank, Mandya Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one-hundred in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring the Ankushapur minor tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of revised estimate for restoring the Ankushapur Minor Tank in Koppa Hobli, Mandya Taluk.

Items of work	Per	Quantity
No. 1. Bund.		
Index stones	Each	20
Register No. stone	"	1
Bench mark stone	"	2
No. 2. Sluice.		
1. Opening bund and refilling with consolidation	C. yd.	88
2. Brick in surki mortar	C. ft.	594
3. Burnt stone slabs 3" thick	S. ft.	84
4. Burnt stone slabs 6" thick	"	83
5. Removing and refixing old jibbits stones, etc.	Lump sum	
6. Removing with surki mortar	Sq.	189
No. 3. Waste Weir.		
6a. Excavation in gravelly soil	C. yd.	539
Do soft rocky disintegrated	"	89
Do do	"	211
7. Burnt brick in surki mortar	C. ft.	274
8. Surki plastering	Sq.	200
9. New stone work	C. yd.	58
10. Dismantling and resetting old stone work	"	40

Y. ASVATHANARAYANA RAO,
Executive Engineer.

HASSAN DIVISION.

Abstract Notification.

The attention of the public is invited to pages 584—585 of Part IV of 26th issue of the *Mysore Gazette*, wherein tenders for restoring the Masavan Ghatta tank, Register No. 257, Channarayapatna Taluk, have been called for.

R. W. SCALDWELL,
Executive Engineer.